



# Economic and Social Council

Distr.: General  
Date: 5 April 2022

Original: English

---

## Economic Commission for Europe

### Inland Transport Committee

### World Forum for Harmonization of Vehicle Regulations

#### 187th session

Geneva, 21-24 June 2022

Item 4.9.5 of the provisional agenda

#### Consideration of draft amendments to existing UN Regulations submitted by GRBP

## Proposal for Supplement 2 to the 01 series of amendments to UN Regulation No. 141 (Tyre pressure monitoring systems)

### Submitted by the Working Party on Noise and Tyres\*

The text reproduced below was adopted by the Working Party on Noise and Tyres (GRBP) at its seventy-fifth session (ECE/TRANS/WP.29/GRBP/73, para. 26). It is based on ECE/TRANS/WP.29/GRBP/2022/2 as amended by informal documents GRBP-75-10 and GRBP-75-33. It is submitted to the World Forum for Harmonization of Vehicle Regulations (WP.29) and to the Administrative Committee (AC.1) for consideration at their June 2022 sessions.

---

\* In accordance with the programme of work of the Inland Transport Committee for 2022 as outlined in proposed programme budget for 2022 (A/76/6 (Sect.20), para 20.76), the World Forum will develop, harmonize and update UN Regulations in order to enhance the performance of vehicles. The present document is submitted in conformity with that mandate.



*Table of Contents, Annex 4, amend to read:*

"4 Test requirements for Tyre Pressure Refill Systems (TPRS) and Central Tyre Inflation Systems (CTIS).....	20"
---	-----

*Paragraph 3.1., amend to read:*

"3.1. The application for approval of a vehicle type with regard to its Tyre Pressure Monitoring System (TPMS) shall be submitted by the vehicle manufacturer or by his duly accredited representative;"

*Paragraph 5.1.1.1., amend to read:*

"5.1.1.1. A Tyre Pressure Refill System (TPRS) or a Central Tyre Inflation System (CTIS) shall be deemed to be equivalent for Type Approval to a Tyre Pressure Monitoring System (TPMS) when it fulfils the requirements of paragraph 5.1.2., 5.1.3. and 5.4. to 5.6. and the test criteria of Annex 4 to this Regulation. In this case TPMS is not required to be installed."

*Paragraph 5.1.1.2., delete.*

*Paragraph 5.1.1.3. (former), renumber as 5.1.1.2. and amend to read:*

"5.1.1.2. If more than one system as defined in paragraphs 2.8., 2.14. or 2.15. has been installed, the system(s) which communicate(s) warning messages to the driver shall be approved according to the requirements of this Regulation.

If more than one system is installed on the vehicle it has to be ensured that no contradictory information is displayed to the driver, e.g. by prioritization."

*Paragraph 5.1.2., amend to read:*

"5.1.2. The effectiveness of the TPMS, TPRS or CTIS fitted on a vehicle shall not be adversely affected by magnetic or electrical fields. This shall be demonstrated by fulfilling the technical requirements and respecting the transitional provisions of UN Regulation No. 10 by applying:

- (a) The 03 series of amendments for vehicles without a coupling system for charging the Rechargeable Electric Energy Storage System (traction batteries);
- (b) The 06 series of amendments for vehicles with a coupling system for charging the Rechargeable Electric Energy Storage System (traction batteries)."

*Paragraph 5.1.6., amend to read:*

"5.1.6. For vehicles of categories M<sub>1</sub> up to a maximum mass of 3500 kg and N<sub>1</sub>

In case of a given warning and if the TPMS is equipped with a reset function but does not detect a minimum pressure as defined in paragraphs 5.2. and 5.3. after executing the reset function, the reset control shall be designed and/or located inside the vehicle in such a way that the risk of an inadvertent reset by vehicle occupants or cargo is reduced.

For vehicles where the TPMS does not detect if the pressure is above a minimum pressure as defined in paragraphs 5.2. and 5.3. after executing the reset function, the TPMS shall include at least measures avoiding a reset if the vehicle did not become stationary after a pressure warning was issued, and either

- (a) Measures avoiding inadvertent reset control operation (e.g. shortly touching on the reset control or continuous blocking of the reset control by vehicle occupants or cargo), or
- (b) An activation by at least two deliberate actions (e.g. in a menu based system).

The manufacturer shall provide in the vehicle owner's handbook, or by any other communication means in the vehicle, the necessary information.”

*Paragraphs 5.4.1., 5.4.2. and 5.4.3., amend to read:*

- “5.4.1. The TPMS/ TPRS/ CTIS shall illuminate the warning signal described in paragraph 5.5. not more than 10 minutes after the occurrence of a malfunction that affects the generation or transmission of control or response signals in the vehicle's TPMS/ TPRS/ CTIS.
- 5.4.2. The malfunction indication warning signal described in paragraph 5.5. shall be illuminated whenever the towed vehicle TPMS/ TPRS/ CTIS provides a malfunction indication via the communication interface described in paragraph 5.6.
- 5.4.3. The malfunction indication warning signal described in paragraph 5.5. shall be illuminated whenever no valid TPMS/ TPRS / CTIS information is available from a connected towed vehicle, that is required to have TPMS/ TPRS/ CTIS, via any communication interface described in paragraph 5.6.”

*Paragraph 5.5.6., amend to read:*

- “5.5.6. The malfunction indication may be the same warning signal as the one used to indicate low tyre pressure. If the warning signal described in paragraph 5.5.1. is used to indicate both low tyre pressure and a malfunction of the TPMS/ TPRS / CTIS, the following shall apply: with the ignition (start) switch in the "on" (run) position the warning signal shall flash to indicate a malfunction. After a short period of time the warning signal shall remain continuously illuminated as long as the malfunction exists and the ignition (start) switch is in the "on" (run) position. The flashing and illumination sequence shall be repeated each time the ignition (start) switch is in the "on" (run) position until the malfunction has been corrected.”

*Paragraphs 5.6.1., 5.6.1.1. and 5.6.1.2., amend to read:*

- “5.6.1. Vehicles of category N<sub>2</sub> or N<sub>3</sub> towing at least one vehicle of category O<sub>3</sub> or O<sub>4</sub> and vehicles of category O<sub>3</sub> and O<sub>4</sub> shall be equipped with a communication interface to exchange TPMS/ TPRS / CTIS data information between towing and towed vehicles. This may be achieved as a wired or a wireless interface, provided that the TPMS/ TPRS/ CTIS equipment in the towing vehicle and in the towed vehicle(s) are compatible.
- 5.6.1.1. The data communication with wired equipment shall be based on the braking electric control line conforming to ISO 11992-1:2019 and ISO 11992-2:2014 and be a point-to-point type using the seven pin connector according to ISO 7638-1:2018 or ISO 7638-2:2018 or an appropriate automated connector.
- Other wired specifications may be used, provided that the TPMS/ TPRS/ CTIS equipment in the towing vehicle and in the towed vehicle(s) are compatible and fulfil the same functional requirements.
- 5.6.1.2. In the case of a point-to-point link between a towing vehicle ECU and a towed vehicle ECU, the towed vehicle ECU, which constitutes part of the point-to-point link, shall provide an interface according to an open standard specification to allow the ECU(s) providing TPMS/ TPRS /CTIS functionality, which does (do) not constitute part of the point-to- point link, to connect, communicate and operate via the towed vehicle ECU which constitutes part of the point-to-point link with ECU of the towing vehicle, i.e. standardised gatewaying. This data communication interface is specified in Part B of Annex 5.”

*Insert new paragraphs 5.7. and 5.7.1. to read:*

- “5.7. Alternative procedure for a subject trailer

- 5.7.1. In the case that a manufacturer chooses to approve a vehicle type of category O<sub>3</sub> or O<sub>4</sub> with regard to TPMS, TPRS or CTIS according to Annex 8 “Alternative procedure for type approval of subject trailer(s)” to this Regulation, then information is utilized from test reports issued in accordance with Annex 7, Appendix 3 and / or Appendix 4 to this Regulation.”

*Annex 2, text below, amend to read:*

“The above approval mark affixed to a vehicle shows that the vehicle type concerned has, with regard to the equipment of a tyre pressure monitoring system, been approved in the Netherlands (E 4), pursuant to UN Regulation No. 141 under approval number 012439. The first two digits of the approval number indicates that the approval was granted in accordance with the requirements of UN Regulation No. 141 as amended by the 01 series of amendments.”

*Annex 3,*

*Paragraph 1.5.1., amend to read:*

- “1.5.1. Test weight.

The vehicle may be tested at any condition of load, the distribution of the mass among the axles being that stated by the vehicle manufacturer without exceeding any of the maximum permissible mass for each axle.

However, in the case where there is no possibility to set or reset the system, the vehicle shall be unladen, but for systems which will automatically raise the lift axle when no load is detected the vehicle shall be laden enough to avoid lifting of those axles. For vehicles of category M<sub>1</sub> up to a maximum mass of 3,500 kg, M<sub>2</sub>, M<sub>3</sub>, N<sub>1</sub>, N<sub>2</sub>, and N<sub>3</sub> there may be, in addition to the driver, a second person on the front seat (if fitted) who is responsible for noting the results of the tests.

The load condition shall not be modified during the test.”

*Paragraph 2.2., amend to read:*

- “2.2. With the vehicle stationary and the ignition locking system in the "Lock" or "Off" position, activate the ignition locking system to the "On" or "Run" position. The ECU controlling the tell-tale shall perform a check of lamp function for the low tyre pressure tell-tale as specified in paragraph 5.5.2. of this Regulation. This last requirement does not apply to tell-tales shown in a common space.”

*Annex 4,*

*Title, amend to read:*

## **“Test requirements for Tyre Pressure Refill Systems (TPRS) and for Central Tyre Inflation System (CTIS)”**

*Paragraph 1.2., amend to read:*

- “1.2. Road test surface

The road shall have a surface affording good adhesion. Testing shall be performed on even ground.”

*Paragraph 1.3.1., amend to read:*

- “1.3.1. Test weight

The vehicle may be tested at any condition of load, the distribution of the mass among the axles being that stated by the vehicle manufacturer without exceeding any of the maximum permissible mass for each axle.

However, in the case where there is no possibility to set or reset the system, the vehicle shall be unladen. For vehicles of category M<sub>1</sub> up to a maximum mass of 3,500 kg, M<sub>2</sub>, M<sub>3</sub>, N<sub>1</sub>, N<sub>2</sub>, and N<sub>3</sub> there may be, in addition to the driver, a second person on the front seat (if fitted) who is responsible for noting the results of the tests.

The load condition shall not be modified during the test.”

*Insert a new paragraph 1.3.3. to read:*

“1.3.3. Rim position.

The vehicle rims may be positioned at any wheel position, consistent with any related instructions or limitations from the vehicle's manufacturer.”

*Paragraph 1.3.3. (former), renumber as 1.3.4. and amend to read:*

“1.3.4. Stationary location

When the vehicle is parked, the vehicle's tyres shall be shaded from direct sun. The location shall be shielded from any wind that may affect the results.”

*Paragraph 1.5., amend to read:*

“1.5. Accuracy of pressure measurement equipment

Pressure measurement equipment to be used for the tests contained in this Annex shall be accurate to at least +/-3 kPa.”

*Insert a new paragraph 2.1. to read:*

“2.1. If a variant of any vehicle submitted for approval is fitted with twin wheels, that variant shall be used for the test and one of the tyres on a twin wheel (the “test tyre”) must be deflated for the refilling test in paragraph 2.5.”

*Insert a new paragraph 2.2. to read:*

“2.2. Before inflating the vehicle's tyres, leave the vehicle stationary outside at ambient temperature with the engine off shaded from direct sunlight and not exposed to wind or other heating or chilling influences for at least one hour for vehicles of category M<sub>1</sub> and N<sub>1</sub> and at least 4 hours for vehicles of category M<sub>2</sub>, M<sub>3</sub>, N<sub>2</sub>, N<sub>3</sub>, O<sub>3</sub> and O<sub>4</sub>. Inflate the vehicle's tyres to the vehicle manufacturer's recommended cold inflation pressure (P<sub>rec</sub>), in accordance with the vehicle manufacturer's recommendation for the speed and load conditions, and tyre positions. All pressure measurements shall be carried out using the same test equipment.”

*Insert a new paragraph 2.3. to read:*

“2.3. With the vehicle stationary and the ignition locking system in the "Lock" or "Off" position, activate the ignition locking system to the "On" or "Run" position. The TPRS / CTIS shall perform a check of lamp function for the low tyre pressure tell-tale as specified in paragraph 5.5.2. of this Regulation. This last requirement does not apply to tell-tales shown in a common space.”

*Paragraph 2.1. (former), renumber as 2.4. and amend to read:*

“2.4. Vehicle conditioning

The pressure reservoir (mounted infrastructure) has to be filled according to UN Regulation No. 13, Series 11, Supplement 16, reservoir pressure limits. The compressed air supply must be granted during the tests according to paragraph 2.5. and to paragraph 2.6. to this Annex.”

*Paragraph 2.2. (former), renumber as 2.5. and amend to read:*

“2.5. Check the systems refill functionality

Check the systems refill functionality for incident-related pressure loss and for detection of a tyre pressure level significantly below the recommended pressure for optimum performance including fuel consumption and safety.

Inflate the vehicle's tyres to the vehicle manufacturer's recommended cold inflation pressure ( $P_{rec}$ ).

Deflate the tyre pressure of one tyre by 20% but not more than 50 kPa below the manufacturers recommended cold inflation pressure ( $P_{rec}$ ). During the deflation the tyre shall not be connected to the pneumatic circuit.”

*Paragraph 2.2.1.(former), renumber as 2.5.1. and amend to read:*

“2.5.1. Check refilling according to Figure 1

Check that within 2 minutes, when the system is operational, the TPRS/ CTIS starts refilling and at least after 2 minutes the low tyre pressure tell-tale, as described in paragraph 5.5. of the Regulation, is “On”.

Refill process shall be completed within 8 min after the refill process has started and the low tyre pressure tell-tale, as described in paragraph 5.5. of the Regulation, is “Off” as soon as the refilling process is completed.

After the refilling process has been completed, check that the tyre pressure is in a range of +/- 5% of manufacturers recommended cold inflation pressure  $P_{rec}$ .”

*Insert a new paragraph 2.5.2. to read:*

“2.5.2. Check refilling according to Figure 2


Check that within 2 minutes when the system is operational the TPRS/ CTIS starts refilling and at least after 2 minutes the low tyre pressure tell-tale, as described in paragraph 5.5. of the regulation, is “On”.

Refill process shall not be completed within 8 min after the refill process has started and the low tyre pressure tell-tale, as described in paragraph 5.5. of the regulation, is “ON” after at least 2 minutes of refilling time.

The deflation rate during the test must be higher than the refilling rate.”

*Figure 1, amend to read:*

**“Figure 1**  
Refilling check




”

Paragraph 2.3. (former), delete.

Figure 2, amend to read:

**“Figure 2**  
Checking system malfunction warning functionality.



”

Insert new paragraphs 2.6., 2.6.1. and 2.6.2. to read:

“2.6. TPRS/ CTIS malfunction detection

- 2.6.1. Simulate a TPRS/ CTIS malfunction, for example, by disconnecting the energy source (electrical power and / or pneumatic pressure) to any TPRS/ CTIS component, disconnecting any electrical connection between TPRS/ CTIS components. When simulating a TPRS/ CTIS malfunction, the electrical connections for the tell-tale lamps shall not be disconnected.
- 2.6.2. Restore the TPRS/ CTIS to normal operation. If the warning lamp has not extinguished, discontinue the test.”

*Annex 5,*

*Part A,*

*Title, amend to read:*

**“A. TPMS/ TPRS/ CTIS data communication between the towing vehicle and towed vehicle(s)”**

*Paragraph 2.1.1., amend to read:*

- “2.1.1. Messages transmitted from the towing vehicle to the towed vehicle, if supported:

<i>Function / Parameter</i>	<i>ISO 11992-2: 2014 reference</i>
Reverse gear status	EBS12 Byte 2 Bit 5-6
Braking system wheel-based vehicle speed	EBS12 Byte 7-8
Time/Date – Seconds	SAE J1939 PGN 65254 TD Byte 1
Time/Date – Minutes	SAE J1939 PGN 65254 TD Byte 2
Time/Date – Hours	SAE J1939 PGN 65254 TD Byte 3
Time/Date – Months	SAE J1939 PGN 65254 TD Byte 4
Time/Date – Day	SAE J1939 PGN 65254 TD Byte 5
Time/Date – Year	SAE J1939 PGN 65254 TD Byte 6
Time/Date - Local minute offset	SAE J1939 PGN 65254 TD Byte 7
Time/Date - Local hour offset	SAE J1939 PGN 65254 TD-Byte 8
Identification data index	RGE12 Byte 5
Identification data content	RGE12 Byte 6

*Note:* Regarding the definition of the parameters of the Time/Date message, there is a known inconsistency between the SAE J1939 and ISO 11992-2:2014 standards. For the purposes of compliance to this Regulation, the Time/Date message definition (PGN 65254) provided in SAE J1939DA 202110 (publication date 21 October 2021) shall be used.”

*Paragraph 2.1.3., amend to read:*

- “2.1.3. Messages transmitted from the towed vehicle to the towing vehicle, if supported:

<i>Function / Parameter</i>	<i>ISO 11992-2:2014 reference</i>
Tyre/wheel identification (for EBS23 pressure)	EBS23 Byte 2
Tyre pressure	EBS23 Byte 5
Tyre/wheel identification (for RGE23)	RGE23 Byte 1
Tyre temperature	RGE23 Byte 2-3
Air leakage detection	RGE23 Byte 4-5
Tyre pressure threshold detection	RGE23 Byte 6 Bit 1-3
Tyre module power supply status	RGE23 Byte 6 Bit 4-5
Identification data index <sup>(1)</sup>	RGE23 Byte 7
Identification data content <sup>(1)</sup>	RGE23 Byte 8

<sup>(1)</sup> Content of the Gateway ECU shall be prioritized

*Paragraph 2.1.4.*, amend to read:

“2.1.4. The towed vehicle ECU transmitting the EBS23 and RGE23 messages shall assemble the EBS23 and RGE23 messages from TPMS/ TPRS/ CTIS content received from the ECU(s) providing TPMS/ TPRS/ CTIS functionality and data from other sources not defined in this Regulation.

Signals, other than Tyre Pressure Status (EBS23 Byte 1 Bit 1-2), within messages EBS23 and RGE23 shall be transmitted with the indication “not available” in case such data is not available.”

*Paragraph 2.2.*, amend to read:

“2.2. When the towed vehicle transmits the following messages, the towing vehicle shall provide a low tyre pressure warning indication to the driver:”

<i>Function / Parameter</i>	<i>ISO 11992-2:2014 reference</i>	<i>Driver warning required</i>
Tyre Pressure Status (For Low Tyre Pressure Warning Indication)	EBS23 Byte 1 Bit 1-2  (00 <sub>2</sub> — tyre pressure insufficient) <sup>(1)</sup>	References to paragraph 5.2.3., 5.2.4., 5.3.4., 5.3.5. and 5.5.2. in this UN Regulation
Tyre/wheel identification (corresponding to Tyre Pressure Status)	EBS23 Byte 2  (XXXXXXXX <sub>2</sub> — actual Tyre/Wheel ID)  OR  (0000000 <sub>2</sub> — Tyre/Wheel ID not defined or wheel not defined and axle > 15 <sub>10</sub> )  OR  (1111111 <sub>2</sub> — Tyre/Wheel ID not available or wheel = 15 <sub>10</sub> and axle = 15 <sub>10</sub> )	References to paragraph 5.2.3., 5.2.4., 5.3.4., 5.3.5. and 5.5.2. in this UN Regulation

<sup>(1)</sup> To be noted that within the definition of EBS 23 “Tyre Pressure Status” ISO 11992-2 qualifies that “an insufficient tyre pressure shall be indicated, if the pressure is outside of a pressure range recommended by the tyre or vehicle manufacturer, to ensure an optimized operation with regard to the

fuel consumption of the vehicle and life time of the tyre.". Therefore, it should be noted that a value of "00<sub>2</sub>" could signify other tyre pressure conditions such as "over-pressure" which are not covered by this regulation."

*Paragraph 2.3.*, amend to read:

"2.3. When the towed vehicle transmits the following messages, the towing vehicle shall provide a TPMS/ TPRS/ CTIS malfunction indication to the driver:

<i>Function / Parameter</i>	<i>ISO 11992-2:2014 reference</i>	<i>Driver warning required</i>
Tyre Pressure Status <i>(For TPMS/ TPRS/ CTIS Malfunction Indication)</i>	EBS23 Byte 1 Bit 1-2  (10 <sub>2</sub> — error indicator)	Reference to paragraph 5.4.1., 5.4.2. and 5.5.2. in this UN Regulation
Tyre/wheel identification <i>(corresponding to Tyre Pressure Status)</i>	EBS23 Byte 2  XXXXXXXX <sub>2</sub> — actual Tyre/Wheel ID)  OR  (0000000 <sub>2</sub> — Tyre/Wheel ID not defined or wheel not defined and axle > 15 <sub>10</sub> )  OR  (1111111 <sub>2</sub> — Tyre/Wheel ID not available or wheel = 15 <sub>10</sub> and axle = 15 <sub>10</sub> )	Reference to paragraph 5.4.1., 5.4.2. and 5.5.2. in this UN Regulation

“

*Paragraph 2.3.1.*, amend to read:

"2.3.1. The towed vehicle shall transmit a Tyre Pressure Status value of "error indicator" within 10 minutes of cumulative driving (in accordance with paragraph 5.4.1. of this Regulation) for any scenario where a valid Tyre Pressure Status (i.e. tyre pressure sufficient or insufficient) cannot be transmitted.

Note that before towed vehicles needed to comply with this Regulation, some of them transmitted Tyre Pressure Status "not available" for some of these scenarios, including when the towed vehicle had no function to perform tyre pressure monitoring. Towed vehicles that are required to comply with this Regulation going forward shall instead transmit "error indicator" for these scenarios.

Note that the towing vehicle would not be required to display a towed vehicle TPMS/ TPRS/ CTIS malfunction indication in the case that valid towed vehicle TPMS information is available on an alternative communication interface."

*Paragraph 2.4.*, amend to read:

"2.4. When a permanent failure is detected in the communication line, the towing vehicle shall illuminate the towed vehicle TPMS/ TPRS/ CTIS malfunction indication signal.

Note that the towing vehicle would not be required to display a towed vehicle TPMS/ TPRS/ CTIS malfunction indication in the case that valid towed vehicle TPMS/ TPRS/ CTIS information is available on an alternative communication interface."

*Paragraph 2.5.*, amend to read:

"2.5. When a valid Tyre Pressure Status is temporarily not available (i.e. unavailable for less than 10 minutes of cumulative drive time), the towed vehicle shall transmit the following messages:

<i>Function / Parameter</i>	<i>ISO 11992-2:2014 reference</i>	<i>Driver warning required</i>
Tyre Pressure Status <i>(TPMS/TPRS/CTIS data temporarily unavailable)</i>	EBS23 Byte 1 Bit 1-2 (11 <sub>2</sub> — not available)	Not applicable
Tyre/wheel identification <i>(corresponding to Tyre Pressure Status)</i>	EBS23 Byte 2 XXXXXXXX <sub>2</sub> — actual Tyre/Wheel ID) OR (0000000 <sub>2</sub> — Tyre/Wheel ID not defined or wheel not defined and axle > 15 <sub>10</sub> ) OR (1111111 <sub>2</sub> — Tyre/Wheel ID not available or wheel = 15 <sub>10</sub> and axle = 15 <sub>10</sub> )	Not applicable

*Note:* paragraph 2.3.1. of part A of this Annex specifies required transmitted values when valid Tyre Pressure Status is unavailable for any longer duration.”

*Annex 5,*

*Part B,*

*Title,* amend to read:

**“B. Data communication between (i) a towed vehicle ECU constituting part of a point-to-point link with the towing vehicle (towed vehicle gateway ECU) and (ii) a towed vehicle ECU(s) providing TPMS/TPRS/CTIS functionality”**

*Paragraph 1.2.,* amend to read:

“1.2. This annex defines requirements applicable to the towed vehicle gateway ECU and the ECU(s) providing TPMS/TPRS/CTIS functionality with respect to the provision of a standard ISO 11898-1:2015 interface and the support of messages defined within ISO 11992-2:2014.”

*Paragraphs 2. to 2.2.,* amend to read:

“2. The towed vehicle gateway ECU that is part of the point-to-point link shall provide an interface with the ECU(s) providing TPMS/TPRS/CTIS functionality complying with data link layer and physical layer in accordance with ISO 11898-1:2015 and ISO 11898-2:2016.

2.1. The CAN bit-rate for the ISO 11898-1:2015 interface shall be 250 kbit/s.

2.2. The ISO 11898-2:2016 bus termination shall be configured on the vehicle in accordance with the guidelines of the vehicle manufacturer for the given installation.”

*Paragraph 2.3.,* amend to read:

“2.3. A power connection shall be made available to the towed vehicle ECU(s) providing TPMS/TPRS/CTIS functionality in accordance with the vehicle manufacturer.”

*Paragraph 2.4.,* amend to read:

“2.4. The towed vehicle gateway ECU shall transmit, towards the towed vehicle ECU(s) providing TPMS/TPRS/CTIS functionality, all messages and signals required to realise a reliable TPMS/TPRS/CTIS function.”

*Paragraph 3.1.*, amend to read:

“3.1. The following functions and associated messages are those that shall be supported by the towed vehicle gateway ECU or towed vehicle ECU(s) providing TPMS/ TPRS/ CTIS functionality as appropriate:”

*Paragraph 3.1.1.*, amend to read:

“3.1.1. Messages transmitted, if supported, from the towed vehicle gateway ECU to the towed vehicle ECU(s) providing TPMS/ TPRS/ CTIS functionality:

<i>Function / Parameter</i>	<i>ISO 11992-2:2014 reference</i>	<i>Reference to paragraphs in this UN Regulation</i>
Reverse gear status (towing vehicle)	EBS12 Byte 2 Bit 5-6	Paragraph 5.6.1.2.
Braking system wheel-based vehicle speed (towing vehicle)	EBS12 Byte 7-8	Paragraph 5.6.1.2.
Identification data index (towing vehicle)	RGE12 Byte 5	Paragraph 5.6.1.2.
Identification data content (towing vehicle)	RGE12 Byte 6	Paragraph 5.6.1.2.
Time/Date – Seconds (towing vehicle)	SAE J1939 PGN 65254 TD Byte 1	Paragraph 5.6.1.2.
Time/Date – Minutes (towing vehicle)	SAE J1939 PGN 65254 TD Byte 2	Paragraph 5.6.1.2.
Time/Date – Hours (towing vehicle)	SAE J1939 PGN 65254 TD Byte 3	Paragraph 5.6.1.2.
Time/Date – Months (towing vehicle)	SAE J1939 PGN 65254 TD Byte 4	Paragraph 5.6.1.2.
Time/Date – Day (towing vehicle)	SAE J1939 PGN 65254 TD Byte 5	Paragraph 5.6.1.2.
Time/Date – Year (towing vehicle)	SAE J1939 PGN 65254 TD Byte 6	Paragraph 5.6.1.2.
Time/Date - Local minute offset (towing vehicle)	SAE J1939 PGN 65254 TD Byte 7	Paragraph 5.6.1.2.
Time/Date - Local hour offset (towing vehicle)	SAE J1939 PGN 65254 TD Byte 8	Paragraph 5.6.1.2.
Braking system wheel-based vehicle speed (towed vehicle)	EBS21 Byte 3-4	Paragraph 5.6.1.2.
Lift axle 1 position (towed vehicle)	RGE21 Byte 2 Bit 1-2	Paragraph 5.6.1.2.
Lift axle 2 position (towed vehicle)	RGE21 Byte 2 Bit 3-4	Paragraph 5.6.1.2.

*Note:* Regarding the definition of the parameters of the Time/Date message, there is a known inconsistency between the SAE J1939 and ISO 11992-2:2014 standards. For the purposes of compliance to this Regulation, the Time/Date message (PGN 65254) definition provided in SAE J1939DA 202110 (publication date 21 October 2021) shall be used.”

*Paragraph 3.1.2.*, amend to read:

“3.1.2. Mandatory messages transmitted from the towed vehicle ECU(s) providing TPMS/ TPRS/ CTIS functionality to the towed vehicle gateway ECU:”

*Paragraph 3.1.3.*, amend to read:

“3.1.3. Messages transmitted from the towed vehicle ECU(s) providing TPMS/ TPRS/ CTIS functionality to the towed vehicle gateway ECU, if supported:”

*Paragraph 3.1.4.*, amend to read:

“3.1.4. For messages defined in section 3.1. of Part B of this Annex, signals shall be transmitted with the indication "not available" in case the ECU(s) does (do) not provide such data.”

*Paragraph 3.2.*, amend to read:

“3.2. The support of all other messages defined within ISO 11992-2:2014 is optional for the towed vehicle gateway ECU and the towed vehicle ECU(s) providing TPMS/ TPRS/ CTIS functionality, unless required by other Regulations.”

*Paragraph 3.3.*, amend to read:

“3.3. The towed vehicle gateway ECU and the towed vehicle ECU(s) providing TPMS/ TPRS/ CTIS functionality shall support diagnostics as per ISO 11992-4:2014.”

*Paragraph 4.*, amend to read:

“4 The towed vehicle ECU providing TPMS/ TPRS/ CTIS functionality shall use the source address 207 of "Other Trailer Devices" as per SAE J1939-71 standard for forwarding TPMS/TPRS/CTIS information with respect to trailer position in a road train like defined in ISO11992-2. “

*Annex 6,*

*Paragraph 2.2.1.1.*, amend to read:

“2.2.1.1. Low Tyre Pressure Warning indication:”

*Paragraph 2.2.1.1.1.*, amend to read:

“2.2.1.1.1. Simulate a towed vehicle low tyre pressure warning and check that the low tyre pressure warning signal specified in paragraph 5.5. of this Regulation is displayed.

The parameters defined in EBS 23 bytes 1 and 2 of ISO 11992-2:2014 shall be transmitted as follows:

<i>Control line signalling</i>	<i>EBS 23 Byte 1 Bits 1 - 2</i>	<i>EBS 23 Byte 2</i>
Low Tyre Pressure Warning indication for tyre/wheel identification number 1,7 (Axle 1, left inner)	00 <sub>2</sub> (tyre pressure insufficient)	00010111 <sub>2</sub> (Tyre/Wheel “1,7”)

”

*Paragraph 2.2.1.1.2.*, amend to read:

“2.2.1.1.2. Simulate a towed vehicle low tyre pressure warning (without known tyre/wheel ID) and check that the low tyre pressure warning signal specified in paragraphs 5.5 of this Regulation is displayed.

The parameters defined in EBS 23 bytes 1 and 2 of ISO 11992-2:2014 shall be transmitted as follows:

<i>Control line signalling</i>	<i>EBS 23 Byte 1 Bits 1 - 2</i>	<i>EBS 23 Byte 2</i>
Low Tyre Pressure Warning indication (without known tyre/wheel ID)	00 <sub>2</sub>  (tyre pressure insufficient)	00000000 <sub>2</sub>  (Tyre/Wheel ID not defined or wheel not defined and axle > 15 <sub>10</sub> )  OR  11111111 <sub>2</sub>  (Tyre/Wheel ID not available or wheel = 15 <sub>10</sub> and axle = 15 <sub>10</sub> )

”

Paragraph 2.2.1.2., amend to read:

“2.2.1.2. TPMS/ TPRS/ CTIS Malfunction Warning:”

Paragraph 2.2.1.2.1., amend to read:

“2.2.1.2.1. Simulate a towed vehicle TPMS/ TPRS/ CTIS malfunction, signalled by the towed vehicle TPMS/ TPRS/ CTIS, and check that the towed vehicle TPMS/ TPRS/ CTIS malfunction indication warning signal specified in paragraph 5.5.6. of this Regulation is displayed.

The parameters defined in EBS 23 bytes 1 and 2 of ISO 11992-2:2014 shall be transmitted as follows:

<i>Control line signalling</i>	<i>EBS 23 Byte 1 Bits 1 - 2</i>	<i>EBS 23 Byte 2</i>
TPMS/ TPRS/ CTIS Malfunction for tyre/wheel identification number 1,7 (Axle 1, left inner)	10 <sub>2</sub>  (Error indicator)	00010111 <sub>2</sub>  (Tyre/Wheel “1,7”)

”

Paragraph 2.2.1.2.2., amend to read:

“2.2.1.2.2. Simulate a towed vehicle TPMS/ TPRS/ CTIS malfunction (without known tyre/wheel ID) and check that the towed vehicle TPMS/ TPRS/ CTIS malfunction indication warning signal specified in paragraph 5.5.6. of this Regulation is displayed.

The parameters defined in EBS 23 bytes 1 and 2 of ISO 11992-2:2014 shall be transmitted as follows:

<i>Control line signalling</i>	<i>EBS 23 Byte 1 Bits 1 - 2</i>	<i>EBS 23 Byte 2</i>
TPMS/ TPRS/ CTIS Malfunction (without known tyre/wheel ID)	10 <sub>2</sub>  (Error indicator)	00000000 <sub>2</sub>  (Tyre/Wheel ID not defined or wheel not defined and axle > 15 <sub>10</sub> )  OR

<i>Control line signalling</i>	<i>EBS 23 Byte 1 Bits 1 - 2</i>	<i>EBS 23 Byte 2</i>
		1111111 <sub>2</sub> (Tyre/Wheel ID not available or wheel = 15 <sub>10</sub> and axle = 15 <sub>10</sub> )

”

Paragraph 2.2.1.2.3., amend to read:


“2.2.1.2.3. Simulate a permanent failure in the communication line and check that the towed vehicle TPMS/ TPRS/ CTIS malfunction indication warning signal specified in paragraph 5.5.6. of this Regulation is displayed.”

Paragraph 2.2.1.2.4., amend to read:

“2.2.1.2.4. Note that the towed vehicle TPMS/ TPRS/ CTIS malfunction indication would not be displayed in the case that valid TPMS/ TPRS/ CTIS information is available on an alternative interface.”

Figure 1, amend to read:


“Figure 1  
Arrangement of device under test and vehicle simulator where TPMS/ TPRS/ CTIS functionality is provided by ECU connected via ISO 11898-1:2015 and 11898-2:2016 interface



”

Figure 2, amend to read:

“Figure 2  
Arrangement of device under test and vehicle simulator where TPMS/ TPRS/ CTIS functionality is provided by ECU connected to towing vehicle



”

Paragraph 3.2.2.2., amend to read:

“3.2.2.2. Follow the test procedure defined in Annex 3 of this Regulation for TPMS or Annex 4 of this Regulation for TPRS/ CTIS and check that the TPMS/ TPRS/

CTIS warning and malfunction signals are transmitted as defined in paragraphs 2.2. and 2.3. of Part A of Annex 5 to this Regulation.”

---